

Bottle Manager
Other Expected Values

Unit 1 Expected Values
3 Instrument(s)

Unit 1 Opacity
Stack Opacity
Span: 80 %
Last Updated: 1/5/2015 9:02:55 AM

Zero Cal
Expected Value: 0 %
Changed: 1/5/2015 9:02:55 AM

Span Cal
Expected Value: 79 %
Changed: 11/4/2014 2:25:26 PM

Unit 1 Flow
Stack Flow
Span: 1500 kscfm
Last Updated: 9/4/2014 9:19:42 AM

Zero Cal
Expected Value: 0 kscfm
Changed: 1/1/2012 12:00:00 AM

Span Cal
Expected Value: 160 kscfm
Changed: 9/4/2014 9:19:42 AM

Unit 1 Low NOx Cable
Stack Low Range NOx cable corrected
Span: 100 ppm
Last Updated: 1/1/2013 12:00:00 AM

Zero Cal
Expected Value: 0 ppm
Changed: 1/1/2013 12:00:00 AM

Span Cal
Expected Value: ppm

Unit 1
Test Unit 1 Stack

Unit 2
Test Unit 2 Stack

Slave Test

Training Room

Edit

Editing Other Expected Values

To edit an expected value, perform the following steps.

WARNING: THE INFORMATION IN THE EXPECTED VALUES FIELD MAY BE BASED ON CALCULATIONS SUBMITTED TO STATE AND FEDERAL REGULATORY AGENCIES. DO NOT MAKE CHANGES TO THE EXPECTED VALUES WITHOUT CONSULTING THE REGULATORY DOCUMENTS TO ENSURE ACCURACY.

1. Select either **Zero Cal** or **Span Cal** of the relevant expected value.
2. Click on **Edit** at the bottom of the pane. A pop-up window will appear
3. Enter the **New Expected Value**.

Click on **OK**.